SECTION 113+000					
DOWN DIP ZONE 1	VOLUME (CU FT)	DENSITY (MT/CU FT)	TONNES (MT)	GRADE (%Pb+Zn)	DILUTED GRADE (%Pb+Zn)
GEOLOGICAL RESERVES (IN-SITU)	685,521	0.107	73,351	8.54	
MINABLE RESERVES (USING 65% RECOVERY)	298,071	0.107	31,894	8.54	7.89

SECTION 113+000				
AY ZONE	VOLUME (CU FT)	DENSITY (MT/CU FT)	TONNES (MT)	GRADE (%Pb+Zn)
GEOLOGICAL RESERVES (IN-SITU)	1,214,340	0.107	129,934	6.40
MINABLE RESERVES	890,298	0.107	95,282	6.40

CURRAGH INC.

SCALE: 0' 100' 200' 300'

SECTION LOOKING NW, SECTION NO. 113+000

01778