



- LEGEND**
- No. 55 Drill Hole
 - Original Depth of Muck
 - Pipe Line 1st Position
 - Pipe Line End Position
 - Retreating Pipe Line for Blowing Tailings
 - Giant Standard Setup
 - Giant Cowboy Setup
 - Dredge Limit and Required Top of Bank
 - Limit of Shallow Stripping
 - Limit of Completed Stripping
 - Creeks and Drains
 - Drift Tailings

STRIPPING PROGRAM

Giants 1 to 15 and 30 to 35 will be set initially. The first group will complete an area that was practically finished in 1940. Giants 30 to 35 will be operated as retreating giants to extend the dredge limit where the bedrock rim had not been reached.

Giants 16 to 29 inclusive cover an area that was partially stripped by Treadgold and will be started as quickly as equipment becomes available.

Giants 34 to 42 inclusive will be set to

first blow the tailings onto the stripped ground or into the old creek channel, then strip the underlying muck to grade. When this is done they will be retreated to a new position and the operation repeated. The giants will be operated progressively downstream in order to maintain and carry the drainage grade toward the left limit.

Panels J-O and O-W will be treated in the same manner as panel B-J. The stripping along the right limit will be well in advance of that on the left in order to prepare tailings disposal room and to insure drainage.

YUKON CONS. GOLD CORP. LTD.
 DAWSON, Y.T.
 No. 10 STRIPPING LAYOUT
 1941 SEASON

Drawn by: A.M.M. & H.V.G.W. SCALE 1"=100'
 Traced by: A.M.M.
 DATE: Dec. 2, 1940. No. 3532
 REVISED: