



**STRIPPING PROGRAM**

**GIANT OPERATION**  
 All giant setups shown are diagrammatic, as the positions will be regularly altered to produce the most efficient muck removal and also according to the equipment available.  
 Giants 1 to 8 inclusive will be set to complete the stripping in an area which was partially stripped in 1935. After which, giants 9 to 12 inclusive will advance blowing the tailings into this stripped area and also in the direction as indicated by the arrows. These giants will then strip the underlying muck to grade.  
 Giants 13 to 21 inclusive covers an area moderately free of tailings. After all muck,

on the areas surrounding the tailings, has been stripped to grade, the tailings will be blown into these stripped areas and the underlying muck removed.  
 Giants 22 to 33 inclusive will be operated similarly to giants 13 to 21. The highway will be protected by leaving a 20 foot berm on either side.  
 Giants 34, 36, and 38 will be first set as shown. They will be retreated to the main pipe line, stripping to grade an aisle about 200 feet wide.  
 Giants 35 and 37 will then advance on the tailings, blowing them into the stripped areas on either side as indicated by the arrows.  
 Giants 39 to 42 inclusive cover an area free of tailings. They will be first set near the drain, stripping to grade as they are retreated to the main pipe line. The muck pillar underlying the pipe lines will be removed as these lines are retreated.  
 Giants 43 to 48 will be operated similarly to giants 39 to 42.

**DRAINAGE**  
 Drainage from giants 1 to 12 will be the same as that of 1935. The stripping of this area must be completed before the thawing starts so as not to pollute the recirculated thawing water.  
 Cross drain "U-V" will be cut to carry the water from giants 13 to 21 into the main drain.  
 Diversion drain "X-Y" will be cut from the main drain to Hunker Creek and dam "Z" constructed before the thawing starts to by-pass the stripping water around the thaw water settling pond.  
 Hunker water will be diverted into the main drain at points "T or W".

**PIPE LINES**  
 Pipe line "A" will be dismantled as soon as stripping is completed in its area and relaid as pipe line "C".  
 When giants 19 to 21 have stripped their area to grade, pipe line "B" will be turned over and extended for giants 22 to 33.  
 Pipe line "D" will be laid if equipment is available and the remaining stripping season warrants it.

**LEGEND**

- Required Top of Bank
- - - Present Dredge Limit
- Stripping Completed
- Tailings on Muck
- Shallow Limit of Stripping
- Creek Ditch or drain
- Pipe Lines - 1st Step
- " " 2nd "
- " " 3rd "
- Giant
- Prospect drill hole with no. above & feet of muck at right
- Prospect shafts are shown square

YUKON CONSOLIDATED GOLD CORP.  
 DAWSON, Y.T.  
**STRIPPING LAYOUT**  
**ARLINGTON**  
**SEASON 1936**  
 DRAWN BY A. M. Nordale  
 DATE Dec. 21, 1935  
 REVISION  
 SCALE 1" = 100'  
 No 3502