Creek Claims from Discovery to No. 36 Above Dis. on ELDORADO CREEK

Claim	Owner: Others	Owner: Co	Length by Govt.	Width by Govt: Upper End	Width by Govt: Lower End	Total Measured Area Sq. Ft.	Area of Value Sq. Feet	Total Aver. Depth in ft.	Cu. Yds: Cu. Yds. of Value	Cu. Yds: Total	Worked Areas in Sq. Ft: Open Cut	Worked Areas in Sq. Ft: Drifted	Solid Area Sq. Ft.	Estimated Average Value: Per Sq. Ft. (cents)	Estimated Average Value: Per Cu. Yd. (cents)	Gross Value	Working Cost: @ Per Cu. Yd.	Working Cost: Total	Net Value @ Per Cu. Yd.	Total Net
0		Y.G.Co.	182 ft	380		81500	81500	20	60300	60300		81500		60	81	48900	35	21000	46	27900
1		Y.G.Co.	499	390	380	198000	Tailings													
2		Y.G.Co.	500	405	380	183000	183000	20	135500	135500	164000	19000		40	54	73200	"	47400	19	25800
2A		Y.G.Co.	14 ft		400	9000	9000	20	6700	6700	9000			40	54	3600	"	2300	19	1300
3			443 ft	490	405	181000	181000	20	134000	134000	141000	40000		50	63	90500	"	46900	28	43600
3A			130 ft	485	490	55000	55000	20	40700	40700	36000	19000		40	54	22000	"	14200	19	7800
4	Pinder		385 ft	430	470	143000	143000	20	106000	106000	125000	18000		40	54	57200	"	37100	19	20100
5	Berry		500			151000	151000	20	112000	112000	124000	27000		50	63	75500	"	39200	28	36300
5A	"		41 ft			10000	10000	20	7400	7400	7500	2500		50	63	5000	"	2600	28	2400
6	"		481 ft			113000	113000	20	83800	83800	89000	24000		40	54	45200	"	29300	19	15900
7		Y.G.Co.	473 ft	180	245	107000	107000	20	79300	79300	101600	5400		50	63	53500	"	27700	28	25800
8		Y.G.Co.	443 ft			96000	96000	20	71000	71000	76000	20000		60	81	57600	"	24800	46	32800
8A		Y.G.Co.	9 ft			3000	3000	20	2200	2200	2000	1000		60	81	1800	"	800	46	1000
9		Y.G.Co.	502 ft																	
9A			14	280		120000	120000	20	89000	89000	98000	22000		100	135	120000	"	31100	100	88900
10		Y.G.Co.	500	285	280															
10A		Y.G.Co.		290	285	151000	151000	20	112000	112000	151000			50	63	75500	"	39200	28	36300
11		Y.G.Co.	503 ft	290	290															
11A		Y.G.Co.	16 ft	290	290	130000	130000	20	96300	96300	69000	61000		60	81	78000	"	33700	46	44300
12		Y.G.Co.	500		290															
12A			8 ft	245		120000	120000	20	89000	89000	99000	21000		60	81	72000	"	31100	46	40900
13		Y.G.Co.	500	365	245															
13A			9 ft	340	365	166000	166000	20	123000	123000	166000			40	54	66400	"	43000	19	23400
14		Y.G.Co.	500	370	340	176000	176000	20	130000	130000	70000	106000		70	94	123200	"	45500	59	77700
14A		Y.G.Co.	11 ft	355	370	5000	5000	20	3700	3700	4000	1000		70	94	3500	"	1300	59	2200
15		Y.G.Co.	495	375	355	165000	165000	20	122000	122000	55000	110000		70	94	115500	"	42600	59	72900
16		Y.G.Co.	488		375	176000	176000	21	137000	137000	56000	120000		50	64	88000	"	47900	29	40100
17		¼ Int Y.G.Co.	425			154000	154000	21	120000	120000	44000	110000		100	129	154000	"	42000	94	112000
17A & 17B			75			39700	39700	21	30800	30800		39700		60	77	23800	"	10700	42	13100
18		Y.G.Co.	487 ft			205000	205000	21	159500	159500	17500	187500		50	64	102500	"	55800	29	46700
19			501 ft	375		170000	170000	21	132000	132000	19000	151000		40	51 57	68000	"	46200	15 22	21800
20	N.A.T.&T.Co.	—	500	275	375	107000	107000	21	83200	83200		107000		75	96	80200	"	29100	61	51100
20A	"	—	6 ft		275	1600	1600	21	1200	1200		1600		75	96	1200	"	400	61	800
21	"	—	500	280	270	89000	89000	21	69200	69200	11000	78000		75	96	66700	"	24200	61	42500
22			495 ft	145 ft	231	125000	125000	21	97200	97200	38000	87000		75	96	93700	"	34000	61	59700
23		Y.G.Co.	469 ft			125000	125000	21	97200	97200	30000	95000		60	77	75000	"	34000	42	41000
24		Y.G.Co.	495 ft			118000	118000	21	91800	91800	65000	53000		40	51	47200	"	32100	16	15100
25		Y.G.Co.	476 ft			100000	100000	21	77800	77800	60000	40000		40	51	40000	"	27200	16	12800
26		Y.G.Co.	447			96000	96000	21	74700	74700	45000	51000		50	64	48000	"	26100	29	21900
27		Y.G.Co.	473 ft			129500	129500	22	105500	105500	57000	72500		60	74	77700	"	36900	39	40800
27A			115 ft			26500	26500	22	21600	21600	10000	16500		60	74	15900	"	7500	39	8400
28			500	299		178000	178000	22	145700	145700	8400	169600		60	74	106800	"	51000	39	55800
29			471	230	305	118000	118000	22	96200	96200	47000	71000		50	61	59000	"	33700	26	25300
30			500			89000	89000	22	72500	72500	55000	34000		50	61	44500	"	25400	26	19100
30A			54 ft			10600	10600	22	8600	8600		10600		50	61	5300	"	3000	26	2300
31			467 ft			101000	101000	22	82300	82300	68400	31600		50	61	50500	"	28800	26	21700
32			482 ft		303 ft	75000	75000	22	61000	61000		75000		50	61	37500	"	21300	26	16200
32A			112 ft			19200	19200	22	15600	15600	11700	7500		50	61	9600	"	5400	26	4200
33			493 ft			111000	111000	22	90500	90500		111000		50	61	55500	"	31600	26	23900
33A			127 ft			29000	29000	22	23600	23600		29000		50	61	14500	"	8200	26	6300
34			500 ft			113000	113000	22	92000	92000		113000		50	61	56500	"	32200	26	24300
35			427			55000	55000	22	44800	44800		55000		60	74	33000	"	15700	39	17300
36			500			64000	64000	22	52000	52000	64000			60	74	38400	"	18200	39	20200
Totals						4,988,600	4,790,600		3,687,300	3,687,300	2,295,100	2,495,500		56	72 ft	2,681,100	35	1,289,400	37 ft	1,391,700

e011079510